220

KOLAR DIVISION.

The 9th March 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar division, up to 5th April 1899 (inclusive), for constructing a Taluk Cutcherry at Srinivaspur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1900.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Taluk Cutcherry at Srinivaspur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Approximate estimate of quantities of work required for constructing a Taluk Cutcherry at Srinivaspur.

Items of work.	*Per.*	*Quantity.*
Earthwork excavation	C. yds.	1,464
Concrete foundation	C. ft.	5,714
Burnt stone in mortar (foundation and basement)	C. ft.	13,535
Burnt brick in mortar (superstructure)	C. ft.	20,318
Burnt brick in mortar, archwork	C. ft.	291
Stone slabs 6″ thick	S. ft.	1,969
Gothic cornice	R. ft.	169
Cornice 9″ deep	,,	806
Perforated parapet wall	R. ft.	70
String course 3″ projection	,,	364
Pointing	S. yds.	13·76
Plastering with chunam	,,	359·19
White and color washing	,,	359·19
Mangalore tile flooring	,,	62·70
Stone flagging with pointing and dressing	,,	14·00
Gravel flooring	C. yds.	72
Bamboo matting outer rind	S. yds.	62·59
Mangalore tile roofing	,,	90·55
Terrace roofing	,,	1·49
Bengal terrace roofing	,,	42·92
Corrugated iron roofing	,,	1 11
Teak wood ceiling ½″ thick	,,	9·44
Zinc gutter valley	No.	8
Teak wood work	C. ft.	1,066
Teak wood pannelled doors	S. ft.	614
Teak wood battened doors	,,	91
Iron door for treasury	No.	1
Gate for main entrance	,,	1
Windows with iron bars with battened shutters	No.	2
Windows pannelled with glazed shutters, iron bars, &c.	S. ft.	724
Cut stone base to wooden pillars	No.	24
Ventilators with iron bars and perforated zinc	,,	19
Ventilators glazed	Sq. ft.	430
Ventilators in front of gables	No.	4
Painting	Sqr.	42·30
Ornamental wooden railing	R. ft.	9½
Moulding, complete, at entrance	L. S. Rs. 25	
Ornamental finials	No.	7
Dias with railing, &c., complete	L. S. Rs. 70	
Prisoners' dock and witness box, complete	,, 55	
Clearing site and levelling ground	,, 50	
Fencing and hedging for compound round Cutcherry	,, 70	
Compensation for land	,, 300	

The 15th March 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar division, up to 15th April 1899 (inclusive) for restoring Kadabur Tank, Reg. No. 179, Goribidnur talak. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1900.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kadabur Tank, Reg. No. 179, Goribidnur taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for restoring Kadabur Tank, Registered No. 179, Goribidnur taluk.

Items.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yds.	19,479
Old stone work	,,	510
New stone work	,,	2,598
Turfing	S. yds.	6,713
Grade stones	Each.	30
B. M. stones	,,	2
Gauge stone	,,	1
Year stone	,,	1
Tank No. stone	,,	1
Sluices Nos. 1 & 2—		
Earthwork	C. yds.	512
Burnt brick in surki	C. ft.	1,746
Burnt stone slabs	S. ft.	442
Chunam plastering	Sqr.	12·64
Gibbet stones	L. S. 20	
Cutting orifice and fixing plug	,, 10	
Waste weir—		
Earthwork	C. yds.	588
Burnt brick in surki	C. ft.	642
Burnt stone, dry	C. yds.	41
Chunam plastering	Sqr.	3·80
Rough stone sujicut	C. yds	84
Burnt stone slabs	S. ft.	329
Anicut—		
Surki concrete	C. ft.	6,229
Burnt stone in surki mortar	,,	5,316
Burnt stone slabs	S. ft.	993
Rough stone in surki mortar	C. ft.	2,294
Shutter for scouring sluice including grove stone	L. S. 100	
Baling water	,, 200	
Excavation in sand and clay, &c.	,, 300	
Flank bund—		
Earthwork	C. yds	1,552
Burnt stone, dry	,,	184
B. M stones	Each.	2
Year stone	,,	1
Head sluice—		
Two vents (3′ × 3′)	..	..
Concrete	C. ft.	389
Burnt stone in surki mortar	,,	1,361
Burnt stone slabs	S. ft.	126
Teakwood shutters, &c., including grove stone, &c., complete	Each.	2
Baling water	L. S. 50	
Excavation, &c.	,, 50	

Items.	Per.	Quantity.
Relieving weir—		
Earthwork	L. S.	60
Burnt brick in surki mortar	C. ft.	2,654
Burnt stone slabs	S. ft.	1,011
Chunam plastering	Sqr.	8·50
Chunam pointing	"	6·56
Concrete	C. ft.	400
Rough stone sujicut	C. yds.	62
Earthwork at flank	"	200
Burnt stone, dry	"	48
Cutting groves	L. S. Rs. 10	
Teakwood shutter, complete	" 40	
Masonry drop at 1000th link—	L. S. Rs. 10	
Excavation	C. ft.	226
Brick in surki	"	253
Hammer dressed stone in chunam	S. ft.	98
Burnt stone slabs	Sqr.	1·00
Chunam plastering	"	1·00
Chunam pointing	C. ft.	22
Concrete		
Channel proper—	C. yds.	9,595
Hard soil	"	803
Soft rock	Each.	1
Mile stone	"	14
Index stones	"	15
Bed grade stones	"	

V. ARUNACHALA MUDALIAR, *Offg Exec. Engr.*

CHITALDRUG DIVISION.

The 8th March 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 15th of April 1899, for constructing a new tank at Parasurampur, Challakere taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1902 A. D.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 (five hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new tank at Parasurampur, Challakere taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.	Unit of work.	Rate per unit.
Bund—		
Digging seat of bund	C. yds.	10,444
Clearing silt (halla)	"	21,413
Earthwork to bund (gravelly soil)	"	39,376
Black cotton soil mixed with gravel	"	86,504
Earthwork from kodi cutting	"	4,127
Black cotton mixed with gravel to be carted from a distance (breached).	"	107,635